

Abadi LNG Project



1 Abadi LNG Project Outline

Project Schedule

3 Marketing and Financing

4 Project Economics / Anticipated Risks and Mitigation

1. Abadi LNG Project Outline



		Gas Field Location Tanimbar Islands Saumlaki
Block Name	Masela Block	Indonesia Masela Block
Location	Arafura Sea in Indonesia	THIO LESIC
Period	Until 2055	Abadi Gas Field
Participating Interest	INPEX 65% Pertamina 20% Petronas 15%	Australia Gas Field Block Darwin 200km
Planned Production Volume	LNG 9.5 MTPA Pipeline Gas 150 mmscfd Condensate 35,000 boed (at peak)	Floating Production Storage and Offloading (FPSO) Gas / Condensate separation Onshore LNG Plant (OLNG LNG 9.5 MTPA
ccs	Entire CO ₂ from the reservoir to be removed and injected. *CCS operation to start from day 1 of LNG production.	Gas Export Pipeline (GEP) Length: 180km
Current Status	Revised Plan of Development with CCS approved in 2023, preparation work for FEED underway	Subsea Umbilicals, Risers and Flowlines (SURF) Water depth: 400-800 meters CCS CO2 injection

2. Project Schedule



Timeline: Aiming to start production in the early 2030s

FEED Preparation
Underway

(Front-End Engineering Design) of Approx. 2 years

FID

EPC

(Engineering, Procurement and Construction) of Approx. 5 years

Production Start

- Preparatory activities for FEED are now underway
 - Onshore / Offshore Geophysical and Geotechnical Survey (G&G Survey)
 - Tender for FEED
 - Environment-related permits, etc.
- FID to be taken after FEED (approx. 2 years), EPC (approx. 5 years) follows, then production starts
- FEED and EPC to be conducted for each package (OLNG, FPSO, GEP, SURF)
- Concurrently with FEED, marketing, financing, land securing and other related activities continue toward FID





3. Marketing and Financing



Continue marketing and financing activities in parallel with FEED toward FID

Marketing



- Conducting marketing activities since 2020
- Executed non-binding MOUs / LOIs with buyers mainly from Southeast Asia (including Indonesia) and East Asia, with their interests exceeding the planned volume
- Continuing engagement with the buyers

Financing



- Conducted market sounding to test the liquidity from commercial banks worldwide in 2024 Q2
- Sufficient liquidity and adequate buffer to fund the project have been confirmed
 ⇒The Majority of expressed amount came from Asian banks.

4. Project Economics / Anticipated Risks and Mitigation



Project Economics Target: IRR mid-10% range

(based on realistic assumptions)

Project Execution Risk

(Green Field Project)

- Make the most of the insights / lessons learned from Ichthys Project experience
- Seasoned professionals from Pertamina and Petronas to be seconded to the project organization

Indonesia Country Risk

- Close communication with Government of Indonesia
- Alignment with Pertamina a state-owned entity

Cost / Schedule

More solid and accurate cost / schedule estimate through FEED

After FEED, INPEX and Government of Indonesia will jointly review the project economics based on the updated cost/schedule to ensure the project has good enough economics